LEGEND

Edging Types


General Legend f	or all drawings
	Site Boundary

Hard Landscape								
Note: Sub-base and base design to be All block paving to meet BS EN 1339: All concrete slab paving to meet BS E	2003 requirements.	ned by engineer. Specification and detail to engineers information.						
Paving Types			Soft Landscape					
Paving Type 1 PT1 Product:	Block Paving - Gateways Lavaro Setts or similar and approved	Product: Addabound	Note: Refer to Engineers drawings and specifications for details on kerbs. All edging are to meet BS EN 1340:2003 requirements. All droppers are to match road kerbs.					
Colour/Size:	Colour Mix: Wit Zwart/Grijis Ĝilsando/Zwart Grijis 420 x 105 x 80mm Supplier: Hardscape or similar approved	Colour/Size: Dune / 3mm Supplier: Addagrip or similar approved	Existing Trees to be Retained Proposed Edible Planting Survey canopy and RPA Survey canopy and RPA Note: Refer to arboricultural drawings for further Survey canopy and RPA					
PT2 Product: Colour/Size:	Lavaro Setts or similar and approved Colour Mix: Wit Zwart/Grijis Gilsando/Zwart Grijis	Paving Type 10 Vehicular Tarmacadam • PT10 • • • • • • • • • • • • • • • • • • •	Proposed Tree Planting Proposed Tree Planting Proposed Tree Planting Proposed Hedge Planting					
Paving Type 3	900 x 300 x 80mm Supplier: Hardscape or similar approved Block Paving - Southern Parking Area	Paving Type 11 Pedestrian Tarmacadam	Size/Spec: Refer to plant schedule Note: Trees to be tagged by landscape architect prior to delivery Size/Spec: Refer to plant schedule All batches of species are to be labeled prior to delivery					
PT3 Product: Colour/Size:	Lavaro Permeable or similar and approved Colour Mix: Wit Zwart/Grijis Gilsando/Zwart Grijis 210 x 105 x 80mm Supplier: Hardscape or similar approved	To Pedestrian and maintenance access loading. Maintenance requirements to be confirmed by others. To Engineer's detail & specification	Proposed Tree Planting in Hard Landscape Grass Type 1 - Amenity Mix Size/Spec: Refer to plant schedule Supplier: Emorsgate Seeds or similar approved Note: Tree pit design to incorporate structural cells to ensure GT1 GT1					
PT4 Product: Size: Supplier:		Paving Type 12 Flag Paving - Balconies & Private Terraces PT12 Product: Slane Flags Colour/Size: Silver Granite / 450 x 450 x 40mm	sufficient rooting volume in achieved. Trees to be tagged by landscape architect prior to delivery Grass Type 1a - Reinforced Amenity Mix					
	Hardscape or equal and approved Slab Paving - Main Square	Image: Supplier: Hardscape or equal and approved Image: Supplicit or equal and approved H	Proposed Fruit Tree Planting Supplier: Fibresand / Emorsgate Seeds or similar approved Size/Spec: Refer to plant schedule Fibresand / Emorsgate Seeds or similar approved Note: Trees to be tagged by landscape architect prior to delivery GT1a					
PT5 PT5 Supplier:	Lavaro Slabs Colour Mix: Wit Zwart/Grijis Gilsando/Zwart Grijis 600 x 600 x 80mm & 900 x 600 x 100mm Hardscape or equal and approved	Product: Tigermulch Colour/Depth: Brown / Installed as per Suppliers guidelines regarding fall zones as appropriate Supplier: Star Rubber or equal and approved	Flowering Lawn Mixture Proposed Multi-stem Tree / Specimen Shrub Planting Size/Spec: Refer to plant schedule Size/Spec:					
Product: Colour/Size:	Setts - Banding Prima Porphyry Grey Mix (Split) 100x100x80mm	PT14 PT14 PT14 PT14 PT14 PT14 PT14 PT14	Note: Trees to be tagged by landscape architect prior to delivery $\downarrow \downarrow \downarrow \downarrow \downarrow \downarrow \downarrow$ Spec: Subject to detailed design; to include protection and drainage layers, filter fleece and substrate of varying depth, typically 80-150mm, to facilitate the establishment of a variety of habitats.					
Supplier:	Hardscape or equal and approved Flag Paving - Communal Areas Slane Flags Silver Granite / 600 x 400 x 50mm	Paving Type 15 Gravel Infill Product: Pea shingle laid over geotextile	$\begin{bmatrix} + & + & + \\ + & + \\ + & + \\ + & + \\ + & + \\ - & + & + \\ \end{bmatrix}$ Size/Spec: Refer to plant schedule Note: All batches of species are to be labeled prior to delivery					
PT8 Product: Colour/Size:	Hardscape or equal and approved Slab Paving - Communal Gardens Lavaro Slabs Colour Mix: Wit Zwart/Grijis Gilsando/Zwart Grijis	Paving Type 16 Composite Decking - Communal Terraces PT16 Product: Millboard Composite Decking Colour/Size: Antique Oak / 3600 x 176 x 32mm	NOTES: Hard surfacing to all vehicular access areas, including required kerbs, to others' design and specification. This is outside of the landscape scope. Refer to highway engineer's drawings for tracking and refuse strategy.					
Supplier:	600 x 600 x 80mm Hardscape or equal and approved	Image: supplier Millboard or equal and approved	Refer to drainage engineer's drawings for drainage strategy and surface water drainage.					

Lighting design: refer to engineers and specialist drawings for lighting specification and location. Final tree location need to be fully coordinated with lighting layout, underground service runs and site drainage. Slope profiles to the open space areas are to be as slack as possible considering access for all.

T1	Edging Type 1 Product: Supplier: Size/Colour: Upstand:	Upstand Kerb Edging [indic.] Cinza Castro Daire Kerb Hardscape or similar approved 200mm / Natural 200mm / To Engineers Specification	ET7	Edging Type 7 - Clay Pavers Product: Atlas Supplier: Hardscape or similar and approved Size: 200x50x65mm Upstand: Flush laid stretcher bond at 90° to paving orientation
T2	Edging Type 2 Size/Colour: Upstand:	Low Retaining Walls *** 200mm at highest point / To Engineers Specification	Boundary Type	es Boundary Type 1 - Gabion Retaining Walls To private terraces
T3	Edging Type 3 Product: Supplier: Size/Colour: Upstand:	Kerb <i>[indic.]</i> PCC Kerb Marshalls or similar approved 125x150x914mm / Natural 100mm / To Engineers Specification		Size/Colour: 500mm ³ baskets / *** Boundary Type 2 - Low Brick Wall To Haven Road frontage
T3a	Edging Type 3a Product: Supplier: Size/Colour: Upstand:	Flush Kerb [indic.] PCC Kerb Marshalls or similar approved 125x150x914mm / Natural 25mm / To Engineers Specification		Boundary Type 3 - Horizontal Slatted Timber Fence To private walkways Material / Size: Cedar / 1800mm high
T4	Edging Type 4 Product: Supplier: Size/Colour: Upstand:	PCC Pin Kerb Pre Cast Concrete Square Pin Kerb Marshalls or similar approved 50x150x915mm / Silver Grey Flush		Boundary Type 4 - Low Brick Walls with Sliding Access Gate To southern parking area Colour: To match building
T5	Edging Type 5 Product: Upstand:	Timber Edging Treated softwood timber board fixed to treated timber stake 50x50x450mm Flush	05	Boundary Type 5 - Timber Fence Type: Horizontal Slatted Featherboard To northern boundary Material / Size: Treated Softwood / 2400mm high
T6	Edging Type 6 Product: Supplier: Size/Colour: Upstand:	Metal Edging ProEdge steel edging EverEdge or similar approved 2.5mm / Corten steel Flush		

FT1	g shown indicatively; refer to Engineers drawings and specification for details of Furniture Type 1 - Bench Product: Clifton 6-slat Backless Bench or similar and approved Supplier: Woodscape or similar and approved Size/Colour: 2000 or custom x 540mm / Hardwood	FT7	Iss Furniture Type 7 - Cycle Hoops Product: Sheffield or similar and approved Supplier: Marshalls or similar and approved Size/Colour: 800mm long / Stainless Steel	FT13	Furniture Type 13 - Timber Pergola Product: Hardwood timber pergola
FT2	Furniture Type 2 - Seat Product: Clifton 6-slat Seat with Backrest or similar and approved Supplier: Woodscape or similar and approved Size/Colour: 2000 x 540mm / Hardwood	FT8	Furniture Type 8 - Tree Grille Product: Corten Steel Square Tree Grille, Ripple or similar approved Supplier: Furns or similar and approved Size/Colour: 1950x1950x10mm / Corten	FT14	Size/Colour: 3000 x 1200x x500mm / Timber Sleeper construction Sleeper construction
FT3	Furniture Type 3 - Seat Product: Clifton 5-slat Wall Seat or similar and approved Supplier: Woodscape or similar and approved Size/Colour: 445mm wide / Hardwood	FT9 ° °	Furniture Type 9 - Removable Bollards Product: Removable steel bollard or similar and approved Supplier: Bailey Streetscene or similar and approved Size/Colour: 900mm high x 101mm dia. / Brushed Stainless Steel	FT15	Furniture Type 15 - Movable Planter Product: Stratum aluminium planter Supplier: Street Design or similar and approved Size/Colour: Various sizes / Jet Black RAL 9005
FT5	Furniture Type 5 - Bench to Raised Planter Product: Cantilever Bench Supplier: Raaft or similar and approved Size/Colour: 460mm wide / Corten steel with Hardwood slats	FT10 ° °	Furniture Type 10 - Bollards Product: Semi-dome Top Steel Bollard or similar and approved Supplier: Bailey Streetscene or similar and approved Size/Colour: 1500mm high x 114mm dia. / Brushed Stainless Steel	FT16	Furniture Type 16 - Planter Product: Planterline or similar and approved Supplier: Raaft or similar and approved Size/Colour: 1200m high x variable
FT6	Furniture Type 6 - Cube Seat Product: Box Bench or similar and approved Supplier: Marshalls or similar and approved Size/Colour: 500x500mm / Escofet Etched Grey	FT11	Furniture Type 11 - Waymarker Signage Product: Waymarker Signage Post Supplier: Bespoke as part of Public Art Size/Colour: Nominally 1800mm high / Corten Steel	FT17	Furniture Type 17 - Bin Product: LBS 112 Square Locakble Bin or similar and approved Supplier: Woodscape or similar and approved Size/Colour: 580 x 580x x 950mm high / Hardwood
		FT12	Furniture Type 12 - Handrails Product: To steps and ramps Colour: Stainless Steel	L1/L2/L3 ©	Indicative Lighting L1: Bollard lighting L2: Surface mounted LED L3: Tree Uplighters * Shown indicatively only and subject to specialist lighting design




This drawing may contain: Ordnance Survey material by permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown Copyright 2017. All rights reserved. Reference number xxxxxxx. OS Open data © Crown copyright and database right 2017 | Aerial Photography © XXXXXXX

 PL01
 15-07-2022
 Issued for Planning
 sw

 Revision
 Date
 Reason
 Dr

 Disclaimer:
 1.
 This drawing is copyright of fabrik Itd. It must not be copied or reproduced without written consent from the owner.
 2.
 Do not scale from this drawing. Only figured dimensions are to be taken from this drawing.
 3.
 All contractors must visit site and be responsible for taking and checking all dimensions related to the works shown on the drawing prior to fabrication or setting out.
 4.
 This drawing uses coloured lines. Please do not rely on a monochrome copy.
 Drawn Checked

External References: • J\D3141 Haven Road, Exeter\05 CAD\01 Autocad\M2 - Models\D3141-FAB-00-XX-M2-L-1006_Legend & Spec



Notes: Refer to fabrik drawings D3141-00-XX-DR-L-1001 to 1xxx for Landscape General Arrangement Drawings

└ Location Plan

feb	k	Lenten House		ECtS et Alton Hampshire prikuk.com W : www.fab			
Project Client							
Haven Ba	en Banks, Exeter Welbeck CP						
Drawing Title							
Landscap	e Gener	al Arrange	ement Leg	lend			
Purpose of Issue			Drawn By	Checked By	Drawn Scale	Date of First Issu	
ISSUED FO	R PLANNI	NG APPRO	VAL	sw/tb	sg	##### @ A1	Jun 2022
Project Number	Origin	Zone	Level	File Type	Role	Number	Revision
D3141	FAB	00	ХХ	DR	1	1000	PL01

 \neg